

**Quotation for Fabrication of shed in front and back side of
Workshop, C Block at PDEU campus**

RFQ: PDEU/FABRICATION/W/2023-24

Name of Bidder: _____

Date: _____

Terms & Conditions:

1. The quotation will be accepted at our below mentioned address by courier/ on-hand delivery on or before 26th June, 2023 at:

**Office of Facility Management & Administration Department,
Amenity Centre, Pandit Deendayal Energy University
Raisan Village, Gandhinagar – 382426**

2. The rate must be inclusive of all taxes and works as per the given specifications.
3. The bidder shall enclose copy of PAN card and GST Registration Certificate.
4. The quotation should in sealed envelope cover.
5. On top of the envelope, the bidder have to mentioned as follow along with name of agency & contact details:

**“Quotation for Fabrication of shed in front and back side of
Workshop, C Block at PDEU campus”**

6. The payment shall be made as per the actual supply of material and after the verification of Engineer.
7. Payment shall be made within 15 days from Invoice raised.
8. The time period for completion of the work is 1 months from the acceptance of the work order.
9. PDEU reserves right to accept or reject bids of any bidder without assigning any reasons.
10. In case of any queries email on: fma@pdp.ac.in

Sign & Stamp

**Quotation for Fabrication of shed in front and back side of
Workshop, C Block at PDEU campus**

Sr No	Particular	Qty	Unit Rate	Amount in Rs
1	<p>Providing, fabricating, assembling, hoisting/ erecting and fixing in position at all heights/ all levels/ all floors/ all shapes & sizes with all leads & lifts using MS Rolled Steel Sections, Hollow/ Tubular sections, all type of sheet/ plate, Bright Bars, deep threaded MS bolts, threaded J bolts, insert plate, support plate etc as per drawing. All confirming to latest relevant IS codes for the work of steel structures like built-up section, staircases, railings, handrail, jali, gates, grills, bracings, grating, corner guard, platforms, brackets, monkey ladder, cattle trap, pipe rack, rungs, false ceiling frame work, Roof canopy, fencing posts, frame work for Screen/ facade etc. including straightening, cutting, bending, bolting and welding the members all as per structural drawings and as per kg detailed specifications (for materials & workmanship) including necessary scaffolding/ staging etc. complete in the situations</p> <ol style="list-style-type: none"> a. Profile Cutting of components to required length/ width and shape/ profile; b. Smooth grinding/ machining of edges/ faces/ all welding joints; c. Necessary welding (electric arc welding) for 	1600 kg		

Sign & Stamp

**Quotation for Fabrication of shed in front and back side of
Workshop, C Block at PDEU campus**

	<p>required weld lengths and sizes.</p> <p>d. Machine drilling of holes for joining/ anchoring. The rate shall include dry sanding, degreasing (wet cleaning) & preparation of rust free surface manually or mechanically, metal putty to make the surface even and smooth, 2 coat zinc chromate yellow oxide primer and 2 coat of enamel paint of approved shade of paint over all the surfaces of the steel sections or as specified in the drawing. (Standard measurements will be paid for as actual cut length used at site).</p> <p>e. Rate shall be inclusive for the cost of anchor fastner, nut, bolt, accessories etc for fixing the elements.</p> <p>Approved Make: TATA/ Jindal/ Asian or equivalent ISI marked</p>			
2	<p>Providing and Fixing Roofing sheet – GI powder coated 0.5mm</p> <p>Approved Make: ISI approved</p>	72 smt		
3	<p>Providing and Fixing FRP sheet 2 – 2.5mm</p>	116 smt		
Total Amount in Rs (including GST)				
Total Amount in Words:				

Sign & Stamp